

गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, इलाहाबाद

टेण्डर नोटिस 13/2018

इलाहाबाद विश्वविद्यालय में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु मुहर बंद निविदा आमंत्रित की जाती है।


कार्य का नाम	अनुमानित लागत (लाख में)	निविदा प्रपत्र का मूल्य (रूपया)	धरोहर धनराशि (प्रतिशत)	कार्य पूर्ण करने की अवधि (दिनों में)
मानव विकास संग्रहालय में दोनों तरफ ब्रिक सोलिंग का कार्य	1,55,548/-	500.00	2.00	30

निविदा प्रपत्र किसी भी कार्य दिवस में दिनांक 06.06.2018 से दिनांक 21.06.2018 अपराह्न 1.00 बजे तक प्राप्त की जा सकती है तथा दिनांक 21.06.2018 समय 3.00 बजे तक कार्यालय में जमा किया जा सकता है। निविदा इसी दिन दिनांक 21.06.2018 को सायं 3.30 बजे उपस्थित ठेकेदारों के समक्ष खोली जाएगी।

धरोहर धनराशि डिमाण्ड ड्राफ्ट/एफ.डी.आर. गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, झूसी, इलाहाबाद के नाम स्वीकार होगा।


नोट: किसी भी या सभी निविदा को निरस्त करने का अधिकार संस्थान के निदेशक, गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, झूसी, इलाहाबाद के पास सुरक्षित रहेगा।

05.06.18


प्रशासनिक अधिकारी

प्रतिलिपि-

1. कार्यालय (लेखा विभाग), को इस आशय के साथ निविदा मूल्य जमा करें।
2. नोटिस बोर्ड इलाहाबाद विश्वविद्यालय/पंत संस्थान।


प्रशासनिक अधिकारी

Govind Ballabh Pant Social Science Institute, Jhusi, Allahabad

NOTE-CONTRACTORS REGISTERED WITH ALLAHABAD UNIVERSITY MAY APPLY

Tender cost: Rs. 500/-

Dr. A. R. Mishra
Administrative Officer

GBPI/Build. Repaire/ /2018

Date-06.06.2018

Tender Form

To

M/s -----

Name of Work: Brick on edge flooring around the Museum building at G.B.Pant Social Science Institute, Allahabad.

Sir,

Please quote your rates for the work named above and send the tender to the Administrative Officer, G.B. Pant Social Science Institute, Jhusi, Allahabad latest by 03.00 p.m. on 21.06.2018 in sealed envelops.

Sl. No.	Description	Quantity	Rate	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10sqm on plan including getting out and disposal of excavated earth upto 50m and lift upto 1.5m, as directed by Engineer-in-charge all kinds of soil.	91.00 m ²		
2	Concrete with 4cm gauge brick ballast fine sand of 1.25 F.M. and cement proportion of 10.5.1 in foundations and under floors including supply of all materials, labour, tools & plants etc. required for proper completion of the work.	9.10 m ³		
3	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12mm cement mortar, including filling the joints with same mortar with common burnt clay non modular bricks in 1:4 (1 cement : 4 coarse sand)	147.00 m ²		
4	Cleaning of Jungle	1 Job		
5	Pointing on brick work or brick flooring with cement mortar 1:3(1 cement:3 fine sand)flush/ruled/struck or weathered pointing. Same qty. of item no. 3	147.00 m ²		
TOTAL				

Yours sincerely,



(A. R. Mishra)

Signature and Full Address
Of the Contractor