

गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, इलाहाबाद

टेण्डर नोटिस 16/2018

इलाहाबाद विश्वविद्यालय में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु मुहर बंद निविदा आमंत्रित की जाती है।

कार्य का नाम	अनुमानित लागत (लाख में)	निविदा का मूल्य (रूपया)	प्रपत्र मूल्य (प्रतिशत)	कार्य पूर्ण करने की अवधि (दिनों में)
मानव विकास संग्रहालय के पोर्टिको की फर्श में लगे कोटा स्टोन का मरम्मत कार्य	1,18,369/-	500.00	2.00	45

निविदा प्रपत्र किसी भी कार्य दिवस में दिनांक 20.08.2018 से दिनांक 31.08.2018 अपराह्न 1.00 बजे तक प्राप्त की जा सकती है तथा दिनांक 31.08.2018 समय 3.00 बजे तक कार्यालय में जमा किया जा सकता है। निविदा इसी दिन दिनांक 31.08.2018 को सायं 3.30 बजे खोली जाएगी। प्रतिभागी ठेकेदार निविदा खुलते समय उपस्थित हो सकते हैं।

धरोहर धनराशि डिमाण्ड ड्राफ्ट/एफ.डी.आर. गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, झूसी, इलाहाबाद के नाम स्वीकार होगा।


नोट: किसी भी या सभी निविदा को निरस्त करने का अधिकार संस्थान के निदेशक, गोविन्द बल्लभ पंत सामाजिक विज्ञान संस्थान, झूसी, इलाहाबाद के पास सुरक्षित रहेगा।

16.08.18


प्रशासनिक अधिकारी

प्रतिलिपि

1. कार्यालय (लेखा विभाग), को इस आशय के साथ निविदा मूल्य जमा करें।
2. नोटिस बोर्ड इलाहाबाद विश्वविद्यालय/पंत संस्थान+समस्त


प्रशासनिक अधिकारी

Govind Ballabh Pant Social Science Institute, Jhusi, Allahabad

NOTE-CONTRACTORS REGISTERED WITH ALLAHABAD UNIVERSITY MAY APPLY

Tender cost: Rs. 500/-

Anjesh Kumar
Administrative Officer

GBPI/Build. Repaire/ /2018

Date-

Tender Form

To

M/s -----

Name of Work: P/L of Kota stone in front of museum portico at G.B.Pant Social Science Institute, Allahabad.

Sir,

Please quote your rates for the work named above and send the tender to the Administrative Officer, G.B. Pant Social Science Institute, Jhusi, Allahabad latest by 03.00 p.m. on 31.08.2018 in sealed envelops.

Sl. No.	Description	Quantity	Rate	Amount
1	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement: 4 coarse sand) 25mm thick	46.01 m ²		
2	Kota stone slabs 20mm thick in risers of step, skirting , dado and pillars laid on 12mm (average) thick cement mortar 1:3(1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete	4.20 m ²		
3	Extra for pre finished nosing in treads of steps of kota stone/ sand stone slab	84 Rmt		
4	Mirror polishing on marble work/granite work/ stone work where ever required giving high gloss finish complete.	97.17 m ²		
5	P/L in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level 1:2:4(1 cement: 2 coarse sand: 4 gradedstone aggregate 20mm nominal size)	3.89 m ³		
6	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metre lead. Same Qty of item No. 1&2 46.01+4.20=50.21 m ²	50.21 m ²		
			TOTAL	

Yours sincerely,


(Anjesh Kumar)

Signature and Full Address
Of the Contractor.